

Which back-plate is required for either hardwired or specific outlets per location?

- **The wall outlets that are available at each location are listed in the Appendices on the Purchasing website under the APC (UPS) Specs.**

How much runtime is required per location?

- **15 – 20 Minutes**

Are PDUs required? If yes, could you provide requirements per location?

- **PDU's may be required based on the location of the UPS's.**
- **Elementary Schools will need to accommodate a Cisco Catalyst 6506 and 2 x Cisco Catalyst 3850, 3750, or 2960 switches in the MDF. Middle Schools will need to accommodate a Cisco Catalyst 6506 or 6513 and 2 additional Cisco Catalyst 3850, 3750 or 2960 switches.**
- **The High Schools needs are listed below.**

EHS

**MDF Stack and two 3850 switches will be in place before ER18, count will include these switches*

MDF – 1 x Cisco 4500X & 7 x Cisco 3850

IDF1 – 8 x Cisco 3850

IDF2 – 8 x Cisco 3850

IDF3 – 7 x Cisco 3850

IDF4 – 6 x Cisco 3850

IDF5 – 7 x Cisco 3850

IDF6 – 6 x Cisco 3850

IDF7 – 2 x Cisco 3750

IDF8 – 2 x Cisco 3750

JEHS

**MDF Stack will be in place before ER18, count will include these switches*

MDF – 1 x Cisco 4500X & 7 x Cisco 3850

IDF1 – 2 x Cisco 3750

IDF2 – 2 x Cisco 3750

IDF3 – 6 x Cisco 3850

IDF4 – 7 x Cisco 3850

IDF5 – 8 x Cisco 3850

IDF6 – 7 x Cisco 3850

IDF7 – 1 x Cisco 3750

ENHS

**MDF Stack will be in place before ER18, count will include these switches*

MDF – 1 x Cisco 4500X & 8 x Cisco 3850

IDF1 – 6 x Cisco 3850

IDF2 – 5 x Cisco 3850

IDF3 – 6 x Cisco 3850

IDF4 – 4 x Cisco 3750

IDF5 – 3 x Cisco 3750

IDF6 – 2 x Cisco 3750

IDF7 – 3 x Cisco 3750

IDF8 – 2 x Cisco 3750

IDF9 – 2 x Cisco 3750
IDF10 – 2 x Cisco 3750
IDF11 – 2 x Cisco 3750

RVHS

MDF – 1 x Cisco 4500X & 7 x Cisco 3850
IDF1 – 6 x Cisco 3850
IDF2 – 9 x Cisco 3850
IDF3 – 8 x Cisco 3850
IDF4 – 1 x Cisco 3750
IDF5 – 7 x Cisco 3850
IDF6 – 5 x Cisco 3850
IDF7 – 1 x Cisco 3850

Is remote management a requirement?

- **Is preferable.**