

# ATTACHMENT D

## SEEDING THE PLAYFIELD

- 1) Irrigation is to be tested prior to seeding for proper coverage. District representatives need to be present. Should there be a need for a punch list it shall be provided by the Project Manager. Upon completion the seed can then be spread throughout.
- 2) It is the Contractor's responsibility to calculate the amount of seed for proper coverage and germination. The District standard for seed is Stover's "Pro Sportsfield Elite". Contractor shall provide 50 lbs. of additional seed for attic stock.
- 3) Contractor shall spread evenly on top of the seed a fine seed cover and program an irrigation schedule for the following (90) day maintenance schedule in which the Contractor shall be responsible for weeding, mowing, edging, and cleaning up of debris. The Contractor shall let the grass grow for a (1) month period before the first mowing and then every (2) weeks there after unless determined by the District that a mowing can take place at an earlier time. The contractor shall be responsible for weeding weekly until the end of the maintenance period upon approval by the District representative.
- 4) The District at any time can call upon the Contractor to provide additional weeding if the District deems it necessary.
- 5) When the grass has reached an approximate (1)" in height, the Contractor shall apply at a lite rate so not to damage or burn the grass "Super Iron Fe".
- 6) Once the grass has filled in and the mowing has begun the Contractor shall determine if the watering schedule will be reduced or adjusted percentage wise.
- 7) Upon completion of the (90) day maintenance period the District shall perform a final punch walk.